

**[NCB-Works/PIClIP-27] Parking Sheds
Annexure – B**

2nd ROUND OF RESPONSES TO BIDDERS' QUERIES

NCB-WORKS/PIClIP-27: Civil Works for Parking Sheds at Sahiwal and Sialkot including Construction of Boundary Wall and Gate, Surveillance and Security System, Guard / Driver and Equipment, Office Building and Allied Works at Sahiwal and Sialkot.

Dated: 16 November 2022

Sr. No	Item reference number	As per Bidding Documents	Reference	Bidders Queries	PMU Reply
Bill No.1 Brick Masonry Boundary Wall					
1	6/5(h)	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): (i) 1500 psi Ratio (1:3:6)	BOQ	Unit of item 100 Sft may check and confirmed.	Unit of item read as 100Cft instead if 100 Sft the revised BOQ is addressed in Addendum No. 03 attached as Annex-A
2	1/1	Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor.	BOQ	-Carriage distance not described in item -Unit of item 1000 Cft may check and confirm	-Carriage of 230 Km from Sargodha to Sahiwal & 270 Km from Sargodha to Sialkot. -Unit of item read as 100 Cft instead of 1000 Cft. The same is addressed in the revised BOQ Addendum No. 03 attached as Annex-A In addition to above, distance for carriage for (MRS. 2 nd Biannual 2022, Chapter #1, Item #1) of crush stone aggregate taken as 230 Km from Sargodha to Sahiwal & 270 Km from Sargodha to Sialkot.
Bill No. 2,3,4,5,6 and B-1.4 Office Building, Guard Room, Entry Gate, RCC Parking Sheds, Drain and Transportation Works					
3	3/17 (a,b,c,d)	Transportation of Earth all types when the total distance including the lead covered in the item of work, is more than 1000 ft.(300 m)	BOQ	Carriage distance not described in item	-Carriage upto 400m or ¼ Mile Refer item 3/17(a) the revised BOQ is addressed in Addendum No. 03 attached as Annex-A

Director
Procurement & Contracts
Program Management Unit
PIClIP, LG&CD Department
Govt. of the Punjab

**[NCB-Works/PICLIP-27] Parking Sheds
Annexure - B**

4	3/17 (a,b,c,d)	Transportation of Earth all types when the total distance including the lead covered in the item of work, is more than 1000 ft.(300 m)	BOQ	Carriage distance not described in item	-Carriage upto 400m or ¼ Mile Refer item 3/17(a) the revised BOQ is addressed in Addendum No. 03 attached as Annex-A
5		With reference to ITB 11.2(g) of Section 2 and Technical Proposal (page no. 52) of Section 4 of tender documents of subject tender. Please clarify that do we have to provide Quality Inspection Plan for the below mentioned point? 1. Quality Control Methods for Building Construction & Steel Structure Works Sir could you please guide for reply of above said Query			Yes, the Bidder has to attach with its Technical Bid the Method / Inspection Plan for the Quality Control for Building Construction & Steel Structure Works as mentioned in Section 4 (Bidding Forms) of issued bidding documents.

Director
 Procurement & Contracts
 Program Management Unit
 PICLP, LG&CD Department
 Govt. of the Punjab
 Director (Procurement & Contracts)

--00000--